H.E.A.R. QUOTE

INVOICE # 005
DATE:5/13/2026

QUOTATION FOR:
Samuel Lee
11519 Blushing Star Court
Charlotte, NC 28215

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Hot Water Heat Pump	● AHRI # 214784826 ● Brand and description Aerotherm G2 ● Model # RE2HP5010PROPH50-T2-RH400 ● Efficiency: 430 ● Tank size: 50 ● Description of installation labor Update gas water heater tank and replace it with an Energy Star Water Heater. - Disconnect and remove the existing water heater if Applicable - Dispose and remove equipment - Disconnect existing water and gas or electrical connection and venting, as required - Install a new gas or electric water heater as specified in this proposal - Set unit in the existing location - Connect to existing, serviceable water piping, gas or electric supply, temperature and pressure relief piping, and venting. - Startup unit and Verify proper operations	$4,000	-$1,750	$2,240
Attic Insulation	● Description of insulation ○ Location of insulation to be installed: Attic ○ Square feet of area to be insulated: 1,431 ○ Type of Energy Star insulation: Owens Corning ○ Current R value:12.15 ○ Ending R value 38	$1,600	-$1,600	$0

Electrical	● Detailed description ○ Materials needed, approximate length of wire: Wires for changing out HVAC and Water Heater from Gas to Electric ○ Which qualified upgrade install requires electrical wiring: HVAC, WH ● Description of labor involved: Electrician will be updating panel and upgrades to electrical because of WH and HVAC	$2,500	-$2,500	$0
Energy Star HVAC	● AHRI # 216030978 ● Outdoor unit ○ Brand and description: MoovAir HP 3 Ton ○ Model # MSHMB36R2AN1 ○ HSPF2: 10 ○ SEER2: 18 ○ Heating capacity: 37000 ○ Cooling capacity: ● Compatible indoor unit description for each outdoor unit ○ Brand and description: MoovAir HP ○ Model # MSHMA36 ○ Description of install labor - Our Exclusive 1 Year Installation Warranty - Evacuate refrigerant system, removes air and water - Ensure proper amount of freon in AC or HP - Complete inspection upon completion - Remove and dispose used equipment - Ensures proper drainage - Clean up work area before leaving worksite - Sealed connections for greater efficiency - Includes County permit - WIFI Thermostat - 10 year compressor warranty - 10 year parts warranty - Equipment Pad to stabilize outdoor unit - Equipment selection and sizing per our Heating & Cooling load calculations. - Honeywell smart thermostat. 5” display comes with Equipment Interface Modulefor 2 wire operation. Comes in White or Black. - PAD 4" Composite Pad - Drip pan for air handler/furnace - New return Air flex install - R-8 Foil backed flex	$15,000	$-8,000	$7,000

	- New supply Air flex install R-8 Foil backed Flex - New return Plenum box made of metal and insulated. Provides proper ductwork fit and an air tight design - New supply Plenum distribution box made of metal and insulated. Provides a perfect fit and a airtight design. - Standard duct work transition - County Permit. Includes permit cost - Reconnect indoor equipment to existing electrical. Reconnect OD equipment to existing electrical Outdoor unit level 2 w/ furnace or air handler			

REBATE	**$0**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Signature

X _____

H.O.M.E. QUOTE

INVOICE # 005
DATE:5/13/2026

QUOTATION FOR:
Samuel Lee
11519 Blushing Star Court
Charlotte, NC 28215

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Energy Star HVAC	● AHRI # 216030978 ● Outdoor unit ○ Brand and description: MoovAir HP 3 Ton ○ Model # MSHMB36R2AN1 ○ HSPF2: 10 ○ SEER2: 18 ○ Heating capacity: 37000 ○ Cooling capacity: ● Compatible indoor unit description for each outdoor unit ○ Brand and description: MoovAir HP ○ Model # MSHMA36 ○ Description of install labor - Our Exclusive 1 Year Installation Warranty - Evacuate refrigerant system, removes air and water - Ensure proper amount of freon in AC or HP - Complete inspection upon completion - Remove and dispose used equipment - Ensures proper drainage - Clean up work area before leaving worksite - Sealed connections for greater efficiency - Includes County permit - WIFI Thermostat - 10 year compressor warranty - 10 year parts warranty - Equipment Pad to stabilize outdoor unit	$15,000	$-15,000	$0

	- Equipment selection and sizing per our Heating & Cooling load calculations. - Honeywell smart thermostat. 5” display comes with Equipment Interface Modulefor 2 wire operation. Comes in White or Black. - PAD 4" Composite Pad - Drip pan for air handler/furnace - New return Air flex install - R-8 Foil backed flex - New supply Air flex install R-8 Foil backed Flex - New return Plenum box made of metal and insulated. Provides proper ductwork fit and an air tight design - New supply Plenum distribution box made of metal and insulated. Provides a perfect fit and a airtight design. - Standard duct work transition - County Permit. Includes permit cost - Reconnect indoor equipment to existing electrical. - Reconnect OD equipment to existing electrical Outdoor unit level 2 w/ furnace or air handler			
Air Seal	● List of each air sealing location: Air Seal attic electrical, plumbing, walls and top plate Penetrations. Attic hatch cover seal & insulation. ● Description of labor involved: 1 Day: 2 or 3 hour job	$1,000	-$1,000	$0

REBATE	**$16,000**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Signature: