H.E.A.R. QUOTE

INVOICE # 009
DATE 5/14/2026

QUOTATION FOR:
Jasmine Sawyer
1208 Crossbend Ct.
Fayetteville, NC 28314

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Hot Water Heat Pump	AHRI # HPS10-50H45DV 2** Brand A.O. Smith Signature 900 50-Gallon Hybrid Heat Pump Water Heater Model # HSPN10-50H45DV Efficiency: 452 Tank size: 50 Description of installation labor Update gas water heater tank and replace it with an Energy Star Water Heater. Disconnect and remove the existing water heater if Applicable Dispose and remove equipment Disconnect existing water and gas or electrical connection and venting, as required Install a new gas or electric water heater as specified in this proposal Set unit in the existing location Connect to existing, serviceable water piping, gas or electric supply, temperature and pressure relief piping, and venting. Startup unit and verify proper operations	$1,750	-$ 1,750	$0
Electrical	Detailed description Materials needed, approximate length of wire: Wires for changing out Water Heater from Gas to Electric Which qualified upgrade install requires electrical wiring: WH Description of labor involved: Electrician will be updating panel, and upgrades to electrical because of WH	$2,000	-$2,000	$0
Attic Insulation	Location of insulation to be installed: Attic Square feet of area to be insulated: 800 ft² Type of Energy Star insulation: Owens Corning Current R value:12.15 Ending R value 38	$1,600	-$1,600	$0

REBATE	**$0**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Jasmine Sawyer (May 14, 2026 14:51:00 EDT)

H.O.M.E. QUOTE

INVOICE # 009
DATE: 5/14/2026

QUOTATION FOR:
Jasmine Sawyer
1208 Crossbend Ct.
Fayetteville, NC 28314

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Energy Star HVAC	AHRI - 217018210 York 3 Ton HP ODU R454B The YC6 models are 16+ SEER2 high-efficiency outdoor HVAC units designed to pair with residential indoor systems for complete home comfort solutions across the U.S. and Canada. MODEL - YH636E2S11 HSPF2 - 8 SEER2 - 16 Heating capacity 36000 BTU Cooling capacity 36000 BTU Outdoor unit: YORK JHE36B5CD2SS1 is a residential air handler designed for heat pump and cooling applications using R-454B refrigerant Model # JHE36B5CD2SS1 - York 2 Ton AHU R454B Description of labor: Includes professional installation with a 1-year labor warranty, system evacuation and refrigerant charging, final inspection, equipment removal/disposal, proper drainage, sealed connections, and full site cleanup. Package includes county permit, Honeywell WiFi smart thermostat, 10-year compressor and parts warranties, equipment pad, drip pan, new R-8 insulated supply/return ductwork and plenums, duct transitions, and reconnection of indoor/outdoor electrical components for the heat pump and furnace/air handler system.	$14,000	-$14,000	$0
Crawl Space insulation and Air Seal	Owens Corning R-19 Wall Unfaced Fiberglass Batt Insulation 77.5-sq ft (15-in W x 93-in L) R-19 unfaced insulation batt, easy 2x6 wall, floor and crawlspace install 800 34 R-Value added per Inch Model #E55P Maximum R-Value -19 Square feet of area to be insulated: 800 ft²	$2,000	-$2,000	$0

REBATE	**$0**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Jasmine Sawyer (May 14, 2026 14:51:00 EDT)

Final Audit Report 2026-05-14

Document created by marshall quick (quick0607@gmail.com)
2026-05-14 - 6:15:21 PM GMT

Document emailed to Jasmine Sawyer (jasmine.sawyer5757@gmail.com) for signature
2026-05-14 - 6:16:34 PM GMT

Email viewed by Jasmine Sawyer (jasmine.sawyer5757@gmail.com)
2026-05-14 - 6:44:22 PM GMT

Document e-signed by Jasmine Sawyer (jasmine.sawyer5757@gmail.com)
Signature Date: 2026-05-14 - 6:51:00 PM GMT - Time Source: server - Signature Appearance Selected: MOBILE_DRAW

Agreement completed.
2026-05-14 - 6:51:00 PM GMT

Adobe Acrobat Sign