H.E.A.R. QUOTE

INVOICE # 005
DATE:8/19/2026

QUOTATION FOR:
Sohanett Ramirez
5213 Walnut Drive
Fayetteville, NC 28304

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Hot Water Heat Pump	● AHRI # 208531076 ● Brand and description A.O Smith ● Model # HPS10-50H45DV ● Efficiency: 452 ● Tank size : 50 ● Description Disconnect, Remove, and Replace the Existing water heater with Energy Star Heat Pump Water Heater - Dispose of removed equipment - Disconnect existing water and gas or electrical connections and venting as required - Install new gas or electric water heater as specified in this proposal - Set unit in existing location - Connect to existing, serviceable water piping, gas or electric supply, temperature and pressure relief piping and venting if applicable - Start the unit and verify proper operation upon completion	$1,750	-$1,750	$0
Attic Insulation	● Description of insulation ○ Location of insulation to be installed: Attic ○ Square feet of area to be insulated: 1,084 ○ Energy Star insulation: Owens Corning ○ Current R-value: 3.75 ○ Ending R-38	$1,600	-$1,600	$0

Heat Pump Dryer	Updating Dryer to an Energy Star Heat Pump Dryer **Model DLHC1455W**	$840	-$840	$0
Electrical	● Detailed description: update outlets and emergency shut offs that are not working as shown in the energy audit ○ Materials needed, approximate length of wire: New outlets, emergency disconnect to be updated and installed ○ Which qualified upgrade install requires electrical wiring: hvac, WH, and panel ● Description of labor involved: professional electrician to update electrical outlets for safety	$2,500	-$2,500	$0
Panel	● Detailed description: Panel is not installed correctly. The panel box is over the breaker and impacting easy shut off. ○ Materials needed: New Panel box, updated breakers ○ Specify main panel or sub panel: Main outside panel ○ Amperage of new service and/or panel: standard 200 Amp	$4,000	-$4,000	$0

REBATE	**$10,690**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Signature

X _____

H.O.M.E. QUOTE

INVOICE # 005
DATE:8/19/2026

QUOTATION FOR:
Sohanett Ramirez
5213 Walnut Drive
Fayetteville, NC 28304

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
HVAC Energy Star	● AHRI # 217016555 ● Outdoor unit ○ Brand and description: York 2 Ton ODU ○ Model # **YH624E2S11** ○ HSPF2: 8 ○ SEER2: 16 ○ Heating capacity 23000 ○ Cooling capacity 23600 ● Compatible indoor unit description for each outdoor unit ○ Brand and description York 2 ton AHU ○ Model # JHE24B5AC2SS1 ○ Description of installing labor: Remove Split System and Replace with EnergyStar Rated Equipment - Disconnect and remove the existing split system HVAC equipment, if applicable, including the outdoor unit and indoor air handler or furnace - Disposal of removed equipment - Install a new split system HVAC system as specified in this proposal - Set and secure the outdoor unit on the existing pad. - Install the indoor air handler or furnace in the existing location - Connect to existing, serviceable duct work, refrigerant piping, electrical connections, condensate	$14,000	$-14,000	$0

	drainage, gas piping (if applicable), and thermostat wiring. - Evacuate, charge, and start the system in accordance with manufacturer requirements - Verify proper operations upon completion			
Air Seal	● List of each air sealing location: door, attic, fan, windows ● Description of which penetrations and air infiltration will be addressed: plumbing, walls and top plate. Also, items in audit penetrations. ● Description of product: Sealant and door sleave	$1,000	-$1,000	$0
Crawl Space Insulation	Description of insulation ○ Location of insulation to be installed: Basement Ceiling ○ Square feet of area to be insulated: 1,084 ○ Energy Star insulation: Owens Corning ○ Current R-value: 0 ○ Ending R-19 Fiberglass blanket along with Install 6 mil vapor barrier under crawl space	$1,000	-$1,000	$0

REBATE	**$16,000**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Signature: