H.E.A.R. QUOTE

INVOICE # 22
DATE:78/26/2026

QUOTATION FOR:
Joshua Goodew
61 Plainview Point Drive
Angier, NC 27501
(919) 628-2137
squosh84@gmail.com

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Attic Insulation	● Description of insulation ○ Location of insulation to be installed: Attic ○ Square feet of area to be insulated: 1,100 ○ Energy Star insulation: Owens Corning loose fill Atticat ○ Current R-value: 10-12 ○ Ending R-38	$1,600	-$1,600	$0
Heat Pump Dryer	Updating Dryer to an Energy Star Heat Pump Dryer **Model: LG - DLHC1455W**	$840	-$840	$0
Electrical	● Detailed description ○ Materials needed, approximate length of wire: New electrical lines, outlets for dryer, electrical equipment for WH, and HP. ○ Which qualified upgrade install requires electrical wiring ● Labor and preventative maintenance and safety	$2,500	-$2,500	$0

REBATE	**$4,940**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Signature

X _____

H.O.M.E. QUOTE

INVOICE # 22
DATE:78/26/2026

QUOTATION FOR:
Joshua Goodew
61 Plainview Point Drive
Angier, NC 27501
(919) 628-2137
squosh84@gmail.com

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
HVAC Energy Star	● AHRI # 217016556 ● Outdoor unit ○ Brand and description: York 3 Ton ODU ○ Model # YH636E2S11 ○ HSPF2:8 ○ SEER2:16 ○ Heating capacity 35000 ○ Cooling capacity 34000 ● Compatible indoor unit description for each outdoor unit ○ Brand and description York 3-ton AHU ○ Model # JHE36B5CD2SS1 ○ Description of installing labor: Remove Split System and Replace with EnergyStar Rated Equipment - Disconnect and remove the existing split system HVAC equipment, if applicable, including the outdoor unit and indoor air handler or furnace - Disposal of removed equipment - Install a new split system HVAC system as specified in this proposal - Set and secure the outdoor unit on the existing pad. - Install the indoor air handler or furnace in the existing location - Connect to existing, serviceable duct work, refrigerant piping, electrical connections, condensate	$14,250	$-14,250	$0

	drainage, gas piping (if applicable), and thermostat wiring. - Evacuate, charge, and start the system in accordance with manufacturer requirements - Verify proper operations upon completion			
Hot Water Heat Pump	● AHRI # 217166009 ● Brand and description A.O Smith ● Model # HPSN10-50H45DV 2** ● UEF: 3.8 ● Tank size: 50 ● Description Disconnect, Remove, and Replace the Existing water heater with Energy Star Heat Pump Water Heater - Disposal of removed equipment - Disconnect existing water and gas or electrical connections and venting as required - Install new gas or electric water heater as specified in this proposal - Set unit in existing location - Connect to existing, serviceable water piping, gas or electric supply, temperature and pressure relief piping and venting if applicable Start the unit and verify proper operation upon completion	$1,750	-$1,750	$0

REBATE	**$16,000**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

Signature: