H.E.A.R. QUOTE

INVOICE # 007
DATE: 7/1/2026

QUOTATION FOR:
Charles McDonald
6313 Tabor Church Road
Fayetteville, NC 28312

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Hot Water Heat Pump	● AHRI # 217166009 ● Brand and description A.O Smith ● Model # HPSN10-50H45DV 2** ● UEF: 3.8 ● Tank size: 50 ● Description Disconnect, Remove, and Replace the Existing water heater with Energy Star Heat Pump Water Heater - Disposal of removed equipment - Disconnect existing water and gas or electrical connections and venting as required - Install new gas or electric water heater as specified in this proposal - Set unit in existing location - Connect to existing, serviceable water piping, gas or electric supply, temperature and pressure relief piping and venting if applicable Start the unit and verify proper operation upon completion	$1,750	-$1,750	$1750
Electrical	Detailed description Materials needed, approximate length of wire: Wires for changing out Water Heater from Gas to Electric Which qualified upgrade install requires electrical wiring: WH Description of labor involved: Electrician will be updating panel and upgrades to electrical because of WH	$1,160	-$1,160	$1160
Panel	Detailed description: Panel is not installed correctly. The panel box is over the breaker and impacting easy shut off. Materials needed: new panel box, updated breakers Specify main panel or sub panel: Main outside panel Description of labor involved: Electrician will be updating the panel and breakers as required by the qualified equipment install.	$3250	-$3250	$3250

Heat Pump Washer/ Dryer	Updating dryer to an Energy Star Heat Pump Dryer Model LG- DLHC1455W	$840	-$840	$840	-$1250	

REBATE	**$14000.00**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0

H.O.M.E. QUOTE

INVOICE # 008
DATE: 7/1/2026

QUOTATION FOR:
Charles McDonald
6313 Tabor Church Road
Fayetteville, NC 28312

COMMENTS OR SPECIAL INSTRUCTIONS:
All work for this project is only for the HOME/HEAR Program. Any additional work or request must be performed separately on a different agreement. All parts and labor are covered under a 1-year warranty. There is additional manufacturer based on the equipment installed.

TECHNOLOGY	DESCRIPTION	UNIT PRICE	REBATE	TOTAL
Crawl Space insulation	● List of each air sealing location (attic, craw Owens Corning R-19 Wall Batt Insulation 77.5-sq ft (15-in W x 93-in L) R-19 unfaced insulation batt, easy 2x6 wall, floor and crawlspace 1300 ft² install. 34 R-Value added per Inch Maximum R-Value -19	$2,000	-$2,000	$0
Attic Insulation	Location of insulation to be installed: Attic Square feet of area to be insulated: 1300 ft² Type of Energy Star Ownes Corning R-19 - R-60 AttiCat PINK Fiberglass Blown-in Insulation ● Description of insulation ○ Energy Star insulation Current R value: 0 Ending R value: 38	$1,600	-$1,600	$0

REBATE	**$3600.00**
SUBTOTAL	$0
SALES TAX	0
TOTAL DUE	$0